

### **ASTM E985 TEST REPORT**

### GR2460 Base Shoe, PG2460 Pad, and PGISO60 Isolator

Rendered to: R&B Wagner, Inc. 10600 W Brown Deer Rd Milwaukee, WI 53224

Report Number:

R17-09-262

Set-up Date:

09/28/2017

Test Date:

09/28/2017

Report Date:

10/09/2017

Project Identification: GR2460 base shoe with PG2460 pad and PGISO60 isolator ASTM E985 Testing

**Project Scope:** Rice Engineering was contacted by R&B Wagner, Inc. to witness testing of their GR2460 base shoe guardrail system, specifically the amount of deflection that would occur in 1/2" thick (9/16") tempered SGP laminated glass (1/4" / 0.060" SGP / 1/4") when pulled to design loads as described in ASTM E985 "Standard Specification for Permanent Metal Railing Systems and Rails for Buildings". On September 28, 2017, Joseph Bauer of Rice Engineering witnessed testing for side and center loaded configurations for a base shoe mounted on concrete. The testing was performed on-site at the R&B Wagner facility and was conducted by Kelly Bauserman.

**Conclusions:** The SGP laminated glass lite was tested to a maximum deflection of 2.353" on the end and 2.087" at the center (ultimate test load of 365 lbf). The allowable deflection was 3.5" at the left and 2.25" at the center. The residual deflection (measured at 90 lbf) was 0.172". The allowable residual deflection was 0.45". There were no signs of deformation on the base shoe or any problems with the pad and isolators, therefore 1/2" thick (9/16") tempered SGP laminated glass <u>passed</u> the ASTM E985 test.

Prepared & Witnessed By:

JOSEPH D.
BAUER
E-43353
LUXEMBURG
WI
SONAL ENGINEER

OCT 0 9 2017

Joseph D. Bauer, Wisconsin P.E.



 R
 &
 B
 WAGNER, INC.

 PO
 BOX 423 | BUTLER, WI | 53007

 10600 W Brown Deer Road | Milwaukee, WI | 53224

 PH
 414.214.0444 | FAX 414.214.8326

### MASTER TABLE

MASTER TABLE								
	ZE	RO POINT FOR C	ALCULA	TIONS				
Height of Rail (h) (in.)	42							
Length of Rail (l) (in.)	48							
Max Left Deflection [h/12] (in.)		3.5						
Max Mid Deflection [(h/24)+(1/96)] (in.)				2.25				
Max Residual Deflection	0.45							
(20% of Max Mid) (in.)		Fron	<b>+</b>					
All imports alread the considerate d	Actual	11011	Actual	<u> </u>	Actual	Left 2 (If		
All inputs should be unadjusted read outs from test	lbsf	Mid	lbsf	<b>Left</b> (If Applicable)	lbsf	Applicable)		
Deflection Reading @ 0 lbsf	0	5.932	0	5.142	0	5.122		
Deflection Reading @ Pre-Load (180 lbsf)	181	4.260	180	3.111	180	2.975		
Deflection Reading @ Released  Test Load (1/2 Pre-load)	90	4.951	90	3.851	89	3.806		
Deflection Reading @ 150 lbsf	151	4.453	153	3.341	151	3.226		
Deflection Reading @ 200 lbsf	202	4.107	200	2.939	201	2.79		
Deflection Reading @ 250 lbsf	250	3.736	248	2.533	250	2.381		
Deflection Reading @ 300 lbsf	299	3.377	300	2.084	302	1.965		
Deflection Reading	265	2.864	265	1 502	265	1 452		
@ <u>Ultimate Test Load (365 lbsf)</u>	365		365	1.523	365	1.453		
Deflection Reading @ Released	91	4.779	93	3.725	89	3.77		
<u>T</u> est <u>L</u> oad (1/2 Pre-load)		Back	<u> </u>					
	I A	Dack	1		T	I . C. O. A.C.		
All inputs should be unadjusted read outs from test	Actual lbsf	Mid	Actual lbsf	Left (If Applicable)	Actual lbsf	<b>Left 2</b> (If Applicable)		
Deflection Reading @ 0 lbsf	0	6.014	0	5.946	0	5.932		
Deflection Reading @ Pre-Load (180 lbsf)	180	4.538	180	4.325	180	4.226		
Deflection Reading @ Released Test Load (1/2 Pre-load)	89	5.289	89	5.096	90	5.010		
Deflection Reading @ 150 lbsf	153	4.702	152	4.555	150	4.472		
Deflection Reading @ 200 lbsf	202	4.336	204	4.130	204	4.028		
Deflection Reading @ 250 lbsf	252	3.999	250	3.741	254	3.607		
Deflection Reading @ 300 lbsf	301	3.681	301	3.312	302	3.208		
Deflection Reading @ <u>Ultimate Test Load (365 lbsf)</u>	367	3.225	365	2.753	366	2.963		
Deflection Reading @ Released  Test Load (1/2 Pre-load)	89	5.267	90	5.034	90	5.019		



R	&c	В	W A G	NE	R,	INC.
PΟ	вох	423	BUT	LER,	W I	53007
10600	) W Bro	OWN D	EER ROAD	MIL	VAUKE	E, WI   53224
PH	414.3	214.(	) 4 4 4	FAX	414.	214.8326

# Railing System Load/Deflection Testing

	0					2
Test Type:	Horizont	al Load to 365 lbsf per	Submitted	KGB	Submitted	09/29/17
	ASTM I	E985 per section 7.1.5	By:	KGD	On:	
Test Focus (Part #s):	PGISO60, PG2	2460, GR2460				

Railing Type: 1/2" SGP glass,  $48"x348"\ 0.519"$  thick, unsupported sides, no cap rail

Railing Specifications: 42" TOR, 4 grips

Test Method: 365 lbsf load per ASTM standards

Test Specifications per ASTM E985		Results						
	System Calculations	Load (lbsf)	Dis	Test Avg.				
Pre Load	180 (lbsf)		Midrail	Left	Left 2	Test Avg.		
rie Loau	160 (1081)	Preload	0.691	0.740	0.831	0.7540		
Released Test Load	90 (lbsf)	RTL	0.000	0.000	0.000	0.0000		
Keleaseu Test Loau		150	0.498	0.510	0.580	0.5293		
<u>U</u> ltimate <u>T</u> est <u>L</u> oad	365 (lbsf)	200	0.844	0.912	1.016	0.9240		
		250	1.215	1.318	1.425	1.3193		
<b>Deflection Specifications Per ASTM E985</b>		300	1.574	1.767	1.841	1.7273		
Max Mid Deflection	(h/24)+(1/96) = 2.25 in	UTL	2.087	2.328	2.353	2.2560		
Max Left Deflection	(h/12) = 3.5 in	RD	0.172	0.126	0.036	0.1113		
Residual Deflection (At RTL)	20% of MD = 0.45 in							

### Notes

Midrail at 0 lbf =5.932

Displacement readings are developed by the difference between the original and final readings of the potentiometer Railing mounted to concrete using the 3/8"x4" DeWALT Screw Bolt +

### Conclusions


Rail meets ASTM Standard for Max. Allowed Deflection for Mid

Rail meets ASTM Standard for Residual Deflection

Rail meets ASTM Standard for Max. Allowed Deflection for Left 1

Rail meets ASTM Standard for Max. Allowed Deflection for Left 2

Horizontal Load Test - Form # EF.03.007.HRZ.R1



## **TEST PHOTOS**

Initial Setup: Mid











Initial Setup: Left









R & B WAGNER, INC.

PO BOX 423 | BUTLER, WI | 53007
10600 W BROWN DEER ROAD | MILWAUKEE, WI | 53224

# Railing System Load/Deflection Testing

Test Type:	Horizontal Load to 365 lbsf per ASTM 985 per section 7.1.5	Submitted By:	KGB	Submitted On:	09/29/17

Test Focus (Part #s): PGISO60, PG2460, GR2460

Railing Type: 1/2" SGP glass, 48"x348" 0.519" thick, unsupported sides, no cap rail

Railing Specifications: 42" TOR, 4 grips

Test Method: 365 lbsf load per ASTM standards

Test Specifications per ASTM E985		Results					
	System Calculations	Load (lbsf)	Disp	Test			
Pre Load	180 (lbsf)		Midrail	Left	Left 2	AVG	
rie Loau		Preload	0.751	0.771	0.784	0.7687	
Released Test Load	90 (lbsf)	RTL	0	0	0	0.0000	
		150	0.587	0.541	0.538	0.55533333	
<u>U</u> ltimate <u>T</u> est <u>L</u> oad	365 (lbsf)	200	0.953	1	0.982	0.9670	
		250	1.29	1.355	1.403	1.3493	
<b>Deflection Specifications Per ASTM E985</b>		300	1.608	1.784	1.802	1.7313	
Max Mid Deflection	(h/24)+(1/96) = 2.25  in	UTL	2.064	2.343	2.047	2.1513	
Max Left Deflection	(h/12) = 3.5 in	RD	0.022	0.062	-0.009	0.0250	
<u>R</u> esidual <u>D</u> eflection (At RTL)	20% of MD = 0.45 in						

### Notes

Midrail at 0 lbf = 6.014 in

Displacement readings are developed by the difference between the original and final readings of the potentiometer Railing mounted to concrete using the 3/8"x4" DeWALT Screw Bolt +

#### **Conclusions**


Rail meets ASTM Standard for Max. Allowed Deflection for Mid

Rail meets ASTM Standard for Residual Deflection

Rail meets ASTM Standard for Max. Allowed Deflection for Left 1

Rail meets ASTM Standard for Max. Allowed Deflection for Left 2

Horizontal Load Test - Form # EF.03.007.HRZ.R1



## **TEST PHOTOS**

Initial Setup: Mid











Initial Setup: Left





