



## THE COMMERCIAL PERSPECTIVE

Restaurant Interior  
Renovation

Tres Palmas Acai  
Charleston, SC






**Wyatt Morris**  
Owner  
Tres Palmas Acai  
Charleston, SC

## THE PROJECT:

Tres Palmas is a niche restaurant in an upscale business environment. Wyatt wanted a classic look to match his brand and the character of the area. We offered to develop this project as a way to “environmentally test” our new PVC-based large format tile sheets. The entire wall design, including the order window cutout and the logo, was designed and programmed into our CNC cutting process.

### Challenges:

- The owner wanted Tres Palmas’ logo to look like it was specially cut out of ceramic tile, an otherwise highly specialized task.
- The wall had to be installed with as few as sheets as possible.
- Being a working restaurant, no dust or debris could be generated.
- Speed of installation was an important consideration. The complete set up, installation and clean up had to occur in a few hours before the store opened to customers.
- The tile had to be installed by only one person.



**“The wall looks fantastic! We are all so excited about it. Thanks so much!”**

# SIX3 TILE

an **aleris** company

119 Grace Avenue  
Lancaster, SC 29720

[www.SIX3TILE.com](http://www.SIX3TILE.com)  
[www.FACEBOOK.com/six3tile](https://www.FACEBOOK.com/six3tile)  
[www.YOUTUBE.com/six3tile](https://www.YOUTUBE.com/six3tile)  
[www.VIMEO.com/six3tile](https://www.VIMEO.com/six3tile)



PROUDLY MADE IN THE USA

## RESULTS:

The installation was flawless - from initial computer cut design and CNC cutting, through installation, grouting and finishing. The entire wall consisted of only 6 large sheets, but resulted in a traditional subway pattern that would have required hundreds of individual ceramic tiles. We use the same installation efficiencies with our tub surround and shower kits.

Wyatt was not only impressed with the results, but very happy that his business' revenue was not affected at all. The entire installation and clean up was finished in only a few hours, long before his doors opened to the public.

## Take Aways:

- Installation of large tile sheets is extremely fast, speeding up workflows exponentially.
- Our PVC-based product is easy to work with, durable and flexible.
- Cutting our tile does not require any saws or special tools. All cutting was accomplished with rotary cutter and a standard utility knife, so no dust was generated.
- Final installed product is indistinguishable from ceramic tile, including the inset logo.



## FOR MORE INFORMATION and TECHNICAL SUPPORT

Additional information about us can be found on our website. You can also connect with us on our Facebook page. We have a variety of instructional videos on our YouTube and Vimeo channels as well as a Resources section on our website, with downloadable installation and maintenance guides, useful tools and other technical information.



All Rights Reserved, Aleris LLC